LEGEND

- ○ Indicates Manhole to be constructed.
- ◎ " Drop Manhole to be constructed.
- ◌ " Existing Manhole
- ◎ " Existing Drop Manhole
- D.E. " Dead End to be constructed
- Pump House " Structures to be constructed
- (Heavy Solid Line) Sanitary Sewer to be constructed.
- (Long Dash Line) Existing Sewer
- S-20 " Line continued on sheet 20 (Plan)
- Pr. 6 " Profile of line on sheet 6 (Profile Sheet)
- El. 72 " Manhole on profile
- " Drop Manhole on profile
- " Existing Manhole on profile
- " Existing Drop Manhole on profile
- El. 95.0 " Elevation above City Datum

Dimensions between manholes are from ℄ to ℄ of Manhole

All Pipe to be Portland Cement Concrete unless otherwise shown on the plan
Cast Iron Pipe to be Class "A"

WORK TO BE DONE

According to plans and specifications hereto attached consists of the construction of a sanitary sewerage system including all pipes, manholes, dropmanholes, dead ends, pipe supports, pumping plant and appurtenances, outfalls,

I-23

Plans 327 D to 336 D inc.
Profiles 337 D to 353 D inc.
Plat 761

SHEET 1	CITY OF SAN DIEGO OPERATING DEPARTMENT	10 SHEETS

PLANS FOR THE CONSTRUCTION OF A SANITARY SEWERAGE SYSTEM IN SOUTH EASTERN PORTION OF CITY

APPROVED _____ CITY ENGINEER
_____ MGR. OF OPERATION

DATE OCT. 24 1925
SCALE 1" = 100'

DRAWN BY Phelps
TRACED BY
CHECKED BY
FIELD BOOKS

CHANGED DATE C.T.

DRAWING NUMBER 327 D

MICROFILMED SEP 11 1963

Sheet 5

Sheet 2